

به نام خدا

شرکت مهندسی خانه های پیش ساخته و مصالح سنتی توسعه صنایع ساخت و ساز پارسیان (سهامی خاص) با تجربه در ساخت و نصب انواع سیستمهای پیش ساخته ساندویچ پانل و سنتی با دارا بودن کادر مجیز و ورزیده و متخصص باسازمانهای مختلف دولتی و بخش خصوصی داخلی و خارجی، شرکتیهای خصوصی داخلی و خارجی که در این مختصر نمی گنجد همکاری داشته و پروژه های مختلفی را به اجرا درآورده است. شرکت خانه های پیش ساخته ساخت و ساز پارسیان در حال حاضر نیز در کشورهای آسیای میانه و آفریقای جنوبی در پروژه های مختلف مشغول به کار می باشد. این شرکت با امکان ساخت و نصب دو نوع سیستم پیش ساخته مشکلات کارفرمایان را به حداقل می رساند.

In the Name of God

Parsian Pre-fabricated Houses and Traditional Materials Engineering Company (P.J.S) with experience in construction and installation of type of pre-fabricated systems of sandwich and traditional panel and possessing skilled and experienced staff and specialists, has been cooperating with various local and foreign government and private organization and companies and is implementing number of projects.

Parsian Pre-fabricated Houses Construction Company at present is also active in the Middle Asian and South African countries in various projects. This company with facilities of construction and installation of two types of pre-fabricated system, has minimize the difficulties of employers.



A) Pre-fabricated systems with installation of parts at site:

In this system walls and other packing parts transported to the site and installed on foundation or chassis with desire and suitable dimensions (capability of replacement and re-installation and replacement of parts).

Advantage:

- Desire dimension in length and width and height and adjustable.
- Tile and ceramic of stone and complete insulation in the sanitary services and kitchen and floor of halls.
- Capability of replacement and re-installation.
- Capability of increase or decrease and/or changes in the inner walls.
- Capability of changing and repairing parts
- Resisted against earthquake

B) Portable Containers System:

With the capability of connecting number of container to each other including residential and administrative container and type of booths and caravans.

Parsian Pre-fabricated Houses Construction company, considering the volume of project I South Africa has taken required action to establish an office with executive taken required action to establish an office with executive staff in South Africa which in case of requirement the respected employers are ready to execute pre-fabricated services.

Ceiling and Wall covering:

Parsian Construction Company while executing house construction and container project, is also an executive of installation of ceiling coverings and industrial halls, shed and poultry with infrastructure and relevant connections.

Specifications of contents of sandwich panels:

sandwich panels are in thickness of 2,4,6,8,10,15 cm and as per the order are manufactured up to the length of 12 meters. Meanwhile, there is 0.5 mm galvanized sheet on both sided and inside it there is also poly porthans, poly stayerol and poly stayerol and poly staerein.

الف) سیستم پیش ساخته با نصب قطعات در محل:

در این سیستم دیوارها و سایر قسمت‌ها بسته بندی و به محل حمل و بر روی فونداسیون یا شاسی به ابعاد دلخواه و مناسب نصب میگردد. (با قابلیت جابجایی و نصب مجدد و تعویض قطعات)

مزایا:

- ابعاد دلخواه در طول و عرض و ارتفاع و قابلیت تغییر
- کاشی و سرامیک سنگ و عایق بندی کامل در سرویس بهداشتی و آشپزخانه و کف سالنها
- قابلیت جابجایی و نصب مجدد
- قابلیت افزایش یا کاهش و یا تغییرات دیوارهای داخلی
- قابلیت تعویض و تعمیر قطعات
- مقاوم در برابر زلزله

ب) سیستم کانکس های آماده قابل حمل:

با قابلیت اتصال چند کانکس به یکدیگر شامل کانکس مسکونی، اداری و انواع کیوسکهای مختلف و کاروان. شرکت خانه های پیش ساخته ساخت و ساز پارسیان با توجه به حجم پروژه در آفریقای جنوبی اقدام به افتتاح دفتر با کادر اجرایی مجهز در کشور آفریقای جنوبی نموده است که در صورت نیاز کارفرمایان محترم اجرای خدمات پیش ساخته در محل می باشد.

پوشش سقف و دیوار:

شرکت ساخت و ساز پارسیان ضمن اجرای پروژه خانه سازی و کانکس، مجری نصب پوشش های سقف و دیوار سالنهای صنعتی و سوله و مرغذاری ها با زیرسازی و اتصالات مربوطه نیز می باشد.

مشخصات متن ساندویچ پانل:

ساندویچ پانل در ضخامتهای ۱۵-۸-۶-۴ سانتی می باشد و تا طول ۱۲ متر برحسب سفارش قابل تولید می باشد. ضمناً ۲ طرف ورق گالوانیزه ۵/۰ میلی متر می باشد و داخل آن نیز پلی پورتان، پلی استایرول و پلی استایرین می باشد.

تجهیزات و امکانات اجرایی

نیروی انسانی:

شرکت ساخت و ساز پارسیان در مدت فعالیت خود از طریق آموزش و استفاده از کار آموزشی در سیستمهای شناخته شده خارجی موفق به تربیت کادری متخصص و مجرب گردیده است.

تجهیزات:

شرکت ساخت و ساز پارسیان با مطالعه و بررسی و بازدید از کشورهای پیشرفته در این سیستم و همکاری با کارخانجات داخلی و خارجی تولیدکننده ابزارآلات و ماشین آلات از بهترین و مدرنترین آنها در جهت سرعت و کارایی بیشتر استفاده می نماید.

Executive Equipment and Facilities

Manpower:

Parsian construction company has been succeeded to train specialized and skilled staff in the foreign recognized systems, during its activities through education and using educational staff.

Equipment:

Parsian construction company, by studying, considering and visiting the advanced countries in this system and cooperating with the local and foreign factories manufacturing tools and machinery, is using the best and most modernized type of them for more acceleration and efficiency.

Personnel	Quality	National
Directors & Managers	5	Iranian
Administration	20	Iranian
Engineering & Technicians	35	Iranian
Skilled Manpower	35	Iranian
Semi Skilled Manpower	42	Iranian
Labor	Depends on Project between 100-200	



ساختمان مهندسين
Engineer building



خوابگاه مهندسين
Engineer Dormitory



خوابگاه مهمان
Guest House

Inner View Of Building

Parsian construction company, by using its best and most suitable type of local products and design in conformity with the Iranian culture, is decorating and designing the inner view of pre-fabricated buildings in the best manner.

نمای داخلی ساختمان

شرکت ساخت و ساز پارسیان با استفاده از بهترین و مناسب ترین نوع تولیدات داخلی و طراحی مناسب با فرهنگ ایرانی نمای داخل ساختمانهای پیش ساخته را به بهترین وجه تزئین و طراحی می نماید.



Dormitory & Camp

خوابگاه و کمپ کارمندی/کارگری

مشکل کمپ و خوابگاه در محل پروژه ها با توجه به سرعت اجرای پروژه ها و عدم امکان ساخت با روشهای سنتی در مناطق جنوبی کشور نیاز به استفاده از سیستمهای پیش ساخته را بیش از پیش نمایان می سازد.

Dormitory & Camp

The problem of camp and dormitory at projects site, considering the executive speed of projects and lack of facilities of construction with traditional methods in the southern regions of the country, make essential the use of pre-fabricated systems more and more.

ساختمان مهندسين
Engineering Building



۱۷

